



**NOTES:**

- ①A GRASS AREAS IN R.O.W. MUST BE RESTORED WITH 4" OF TOP SOIL AND SOD
- ①B SEE PAVEMENT RESTORATION DETAIL FOR PATCHING REQUIREMENTS
- ②A UNDER GRASS AREAS BACKFILL WITH EXCAVATED MATERIAL PLACED AND COMPACTED IN 12" LIFTS
- ②B UNDER, AND WITHIN 2' OF PAVEMENT, CURB & GUTTER, AND SIDEWALK, BACKFILL WITH CA-6 MATERIAL IN 9" LIFTS COMPACTED TO 95% MAX. DENSITY
- ③ CA-11 STONE BACKFILL PLACED AND COMPACTED IN 6" LIFTS
- ④ CA-11 STONE BEDDING. MINIMUM THICKNESS = 1/4 OF THE OUTSIDE DIAMETER OF THE PIPE, BUT NO LESS THAN 4"
- ⑤ UNSUITABLE MATERIAL TO BE REMOVED AT THE DIRECTION OF VILLAGE ENGINEER, AND REPLACED WITH COMPACTED CA-11 STONE
- ⑥ THE TRENCH WIDTH SHALL BE AT LEAST 18" WIDER THAN THE OUTSIDE DIAMETER OF THE PIPE

**Village of Mount Prospect**

**Public Works Department  
1700 W. Central Rd.**

**TRENCH SECTION DETAIL**

**Last Revised: 8-09**